

- 100mm away from the four edges of the foundation;
- 2. The pre-embedded pipeline should be in line with the opening position of the base board of the EV charger, which avoids the problem of inconsistency between the pipeline and the opening hole, thus making it impossible to construct;
- 3. The installation is fixed by Φ 12 pre-embedded parts or expansion bolts, stainless steel or hot-dip galvanised;
- 4, the basement does not allow excavation for pre-embedding, the foundation depends on the
- 5. The size reserved behind the cabinet during installation should be greater than or equal to the width of the cabinet.

